

Section I – X Best Practise Guide for TTM relating to Land Surveying

Inspections and other short-term activities carried out for Land Surveying purposes.

June 2020 - Version 4.0



Group Name: Survey and Spatial New Zealand

Contributing Organisations: Consulting Surveyors New Zealand and Land Information New Zealand

Endorsed on behalf of S+SNZ by Ashley Church, Chief Executive



Contents

Inspections and other short-term activities carried out for Land Surveying purposes1
Group Name1
Contributing Organisations1
CoPTTM Submission
Section A - Introduction & General
Proposal5
Training & Competency – Submission proposal7
Appendix
Sample Standard Operating Procedure: Survey and Inspection for TTM Engagement- Approvals and Implementation10
Sample Survey and Inspection Generic Proforma10
Sample Engineering Exception Decision: Surveying within the carriageway on Level LV and Level 1 Roads
Sample Survey and Inspection Traffic Management Diagrams
Sample Survey and Inspection Checking Process for Generic Checking Process for Generic TMPs Incorporating Onsite Record Form



CoPTTM Submission

Section A - Introduction & General

Who are Survey and Spatial New Zealand

Survey and Spatial New Zealand (S+SNZ, legally incorporated as the New Zealand Institute of Surveyors) represents surveyors and spatial professionals. We are a stakeholder across a wide range of government policy areas and the sector including housing development, land subdivision, construction, infrastructure, spatial information, and resource management. Our members are professionals responsible for the preparation of Cadastral Survey Datasets in accordance with the Surveyor-General's Rules for Cadastral Survey 2010, (the Rules) established under section 49 of the Cadastral Survey Act 2002 (the Act).

Why are Surveyors access the Road Reserve and Road Corridor?

At its most basic, surveying is taking measurements to determine the position of a survey mark, or other feature. A significant proportion of all survey work is undertaken within the road corridor and there appears to be a general assumption that if a surveyor is working within the road corridor, it must be for some road construction activity. This is correct in a number of cases, as surveyors are called upon to define the legal extent of the road, as well as giving spatial certainty to the physical roads themselves and the other assets that occupy space within the corridor. However, overall, this type of survey is a very small proportion of a surveyor's work.

It is much more likely that a surveyor is accessing the survey network, a very important but inconspicuous layer of infrastructure. Part of this countrywide network of survey marks is contained within the LINZ Geodetic Database. This is the control layer and it comprises approximately 130,000 geodetic survey marks that are mostly contained within the road network. In addition to these marks, there are many more cadastral survey marks that are recorded on old cadastral survey plans.

Much of this network of survey marks is contained within the road reserve because it is an area that is currently publicly accessible, and it is likely to remain that way. Also, the clear space, and even grades necessary for public movement, permit longer sightlines than are generally possible on private land. So, a surveyor's primary purpose in accessing the road reserve is not to execute road works, but to access the survey network. The geodetic part of this network is owned by the NZ government, and it is maintained by an annual programme of geodetic surveys.

Cadastral Surveys

While there are many different types of survey, one that is common and is worth mentioning is the cadastral survey. These surveys are primarily concerned with establishing the position of existing legal boundaries and placing marks to delineate new and existing legal boundaries. The conduct of these surveys is controlled by legislation, mostly within the Cadastral Survey Act 2002 and its subsidiary regulations.



Our NZ cadastral system is based on the evidential proof of finding existing survey marks to confirm a survey fits within the verified framework. Therefore, a surveyor is required to locate and observe old survey marks to define the position of a boundary. The best available definition of the boundary is required and so the observations should be made to the nearest and most reliable of the existing survey marks that remain. Therefore, the search for old marks generally progresses outwards from those most relevant. Since it is not possible to predict whether a mark that was placed years earlier still remains, and is in its original position, it is also not possible to know where a search may lead in advance. Older survey marks were often buried in the berm and so to locate and observe to them it is necessary to dig a small hole with hand tools such as a spade or metal bar to expose the mark. Typically, these would be approximately 200mm deep, so they would be exposed, observed and covered over again within a few minutes.

When looking for marks from older surveys, in areas where the road has been upgraded, the search can be extensive often covering many kilometres of the road corridor. The movement over this distance can occur quite rapidly, as the search for one mark may only take a few minutes and marks many be hundreds of metres apart. With such a dynamic and highly unpredictable degree of movement, a cadastral survey is very different to the survey for a construction project. Experience shows that it is pure folly to attempt to plan all but the simplest cadastral surveys from the office. Similarly, dates can be unpredictable, as either the site conditions, or the weather can be unfavourable. Things as mundane as a vehicle parked in the wrong location, blocking sight lines or obstructing survey marks may affect the survey. Due to the unpredictable nature of cadastral surveying, it is imperative that surveyors can operate under a generic traffic management plan that can be adapted as required.

A Space for Surveyors

Surveyors have been undertaking these surveys in NZ, since its first exploration by Europeans. Over this time they have developed a fundamental background knowledge of how to operate safely within the road corridor. As a reaction to the invention and rise in the number of motor vehicles, surveyors have looked for safer locations to place new survey marks. Additionally, procedures have continued to evolve with the arrival of each new advance in technology, such as electromagnetic distance measurement (EDM) and GPS.

Surveyors consider the road to be their natural working environment, where they can mitigate the risks to work safely. In contrast, generally RCAs have little to no understanding of the nature of a surveyor's work. Consequently, they tend to require traffic management solutions that are appropriate to static construction sites, as opposed to the surveyor's short term, highly mobile operation. Since the set up and break down of sites are higher risk activities, this approach is likely to increase the risk and exposure to surveyors.

Over the years, with the increasing use of the road corridor for vehicles and more underground services, the available space for surveyors to operate has reduced. To avoid conflict with vehicles, services and pedestrians, surveyors have adapted to placing a number of marks in the concrete kerb or channel. Additionally, these areas are usually stable and often last longer than footpaths.

The one drawback of setting up a tripod over a mark in the kerb or channel is the need to place one or two tripod legs in the edge of the carriageway. This is often viewed as problematic from a



traffic management point of view because of the arbitrary view that the whole carriageway is for vehicle movement. However, on Low Volume and Level One roads with parking lanes or shoulders, this practice has proved to present minimal risk to normal traffic operations. Although, on busier roads, particularly where traffic lanes are close to the kerb, we identify this is not a safe option without lane closures, or similar measures.

While the kerb and channel is a favoured position, that avoids many of the conflicts, other positions are; within the footpath, vehicle crossings, berms, parking bays, the shoulder, traffic islands and within a live lane, although this is typically avoided unless absolutely necessary and provided the environment is safe to do so. In selecting the position of a new survey mark, surveyors must balance the safety aspects with the requirements of the survey. For example, survey marks are often placed to meet a specific need, such as line of sight to place a boundary mark or survey existing features. For GPS work, an unobstructed skyline is the optimal situation to gain non-compromised satellite signals to ensure that both survey accuracy and spatial certainty is achieved. The road environment is continually changing, and surveyors continue to evolve with it. A fairly recent example, particularly in and around central city areas, is the number of new cycle lanes that are being created within existing road corridors.

Typical Survey Equipment

Most survey equipment is either mounted on a surveyor's tripod or a pole, which is either handheld or braced for a short period with small supporting legs. Usually this will be attended in order for it to be operated and if required it can be relocated at short notice. This description would include a non-robotic total station, a theodolite or a level on a tripod as well as a reflective prism or GPS rover on a pole.

However, some equipment is more automated, and it may be only partially attended after it has been set up. This would include equipment such as a robotic total station, a survey prism target, a laser scanner, or a GPS base station, which would all typically be mounted on a surveyor's tripod.

Modern equipment is light weight and while it is often expensive, it can be described as frangible. While surveyors prefer to remain separated from pedestrians, this is to prevent disturbance or damage to the equipment once it has been setup. In contrast to the majority of construction work, there is minimal danger to a pedestrian walking too close to survey equipment.

Proposal

- I. Amend section D7.6 to include specific guidelines for land survey activities
- II. Amend section F to include specific TMDs for land survey activities Or
- III. Include an addition to CoPTTM Section I to provide a guideline including TMDs for spactial survey activities



Submission breakdown

The current standard/guideline	Surveying industry feedback/remarks	Proposed Solution
 The TC Inspector warrant; designed for off road inspections with the added proviso that, on lane inspections could be carried out "infrequently" (max of 4) 	Cover all aspects required for inspectors to do both on and off lane inspection, without a limitation.	CoPTTM Training & Competency Model Specialist TTM Activities Proposals as outlined in this document
The TC Inspector must be briefed by an STMS	To date, most companies have had an 'in house STMS' to cover the required briefing by an STMS. New training pathway means huge cost implications in order to obtain a practising STMS warrant. Universal STMS covers all learning outcome associated with	CoPTTM Training & Competency Model Universal STMS delivers the briefing. Proposals as outlined in this
There is one TMD in the code that illustrates an inspection activity	the role required. The current TMD does not cover all survey specific activities and is therefore not fit for intended purpose in this context. A specific guide for the industry would be well received to create consistencies. The need for a set of generic	document Section 'handbook' or best practice guide created. See proposed TMP and SOP Addition to Section I of CoPTTM
	inspection TMDs that cover the scope of works that can be undertaken as an 'inspection and/or non-invasive' activity.	for approved generic inspection TMDs See proposed TMP
On-site record and GTMD checking process would need to be complete for each location visited.	The current forms are not fit for purpose if multiple short-term site visits are required over the duration of a normal work period.	Addition to FORMS section of NZTA – CoPTTM website with new form covering onsite monitoring for inspections <i>Please see proposed form</i>
State Highways Interim TMDs restricting the use of a Generic TMP.	Surveyors to apply a risk-based assessment of the road environment in order to still use generic TMP on State Highways when risk result permits the activity.	Robust risk assessment tool created for surveyors to assist in decision making for Generic TMPs on State Highway Networks.

Important elucidation


This submission is applying to still allow the TC inspector to conduct inspection activities on the level 3 (Category C) Roads (with minor adjustments outlined), however the generic TMP submission will not include level 3 (Category C) Roads or inspections on State Highways. These roads are to be treated with a site specific TMP in accordance with the RCA, NOC Representative or District Council RCA guidelines.



Training & Competency – Submission proposal Proposed Training pathway

The group would like to propose that a Universal STMS can conduct the briefing to TC inspectors. The Competency objectives and knowledge for a Universal STMS aligns very well with the role they will assume when briefing a TC Inspector before undertaking works, to list a few;

- Health and safety processes relevant for the role
- Knowledge of their role and responsibility
- Lead and give direction to their crew and visitors
- Understanding the TMP
- Understanding the principles of TMP implementation
- Understand contingency plans
- Ability to assess risk (decide what it is and severity)
- Basic Leadership (anticipation, planning, maintaining standards, delegation, safety for the team and others, supervision)
- Understand the minimum requirements of a site safety briefing/induction





Inspector Profile – Proposed

Block of I Learning:	Inspector	Who it is for? A person carrying the edgeline or inf footpaths and ber lane for less than Universal STMS.	erred edgeline i ms and/or acce	ncluding ssing the live
Prerequisite:	No prerequisite			
Objective	This qualification enables the ho Universal STMS	-		-
Knowledge of basic (CoPTTM elements covered	Assessment method	Pass criteria	Misc.
 role Knowledge of barrole Follow, read TMF Complete paperw Hazard ID & Basia assessment and Take corrective at Working with starreinforcing perfo Site access / Bride Preserving safety Understanding or different kinds of conducted under Maintain pedestre How to utilise velocitoria safety at the safety at the	ic understanding of risk treatment actions (to make site safe) ff (e.g. providing direction, rmance) efing visitors y zones (No go zones) f inspection activity and the f operations that can be	Knowledge tests during training Scenario dealing with common inspection situations – can complete multiple times if required	100% pass	Workshop delivered by: NZTA approved Trainer Refresher • No refresher workshop • Refreshed by briefing from an STMS • 3-year reassessment of practical Time • 1 day theory/ knowledge • Plus on-site practical Related unit standards
Identify / recognise o	correct PPE	Visual check onsite – TTM assessor HiVis worn correctly	Correctly wearing all PPE as per site requirements	
	kills Element to be covered	Assessment method	Pass criteria	Misc.
 Shoulder close Undertake 2 inspect 1. One on a cat under 65kph 	egory A Road (LV, L1 or L2	Observed by TTM Trainer or TTM Assessor • Must undertake 1 inspection activity (including paperwork) for category A and B road environments • TTM Trainer or TTM Assessor determines if the candidate is competent	100% to standard	



Summary of operation and personnel

Type of Road	On Shoulder, berm, or footpath – no time limit	On live lane – up to 5mins	Over 5mins
Low Volume (Any speed)		 Spotter Optional – can be a one-person operation: Working under an approved TMP Briefed by a Universal STMS Holds a current practising qualification as a TC inspector, TC, or STMS 	
Level 1		Spotter Required – Minimum two-	
Level 2 – Low speed	Spotter Optional – can be a one-person operation: • Working under an approved TMP • Briefed by a Universal STMS • Holds a current	 person operation: Working under an approved TMP Briefed by a Universal STMS Holds a current practising qualification as a TC inspector, TC, or STMS 	Inspection not permitted. Must use a higher
Level 2 – High speed	practising qualification as a TC inspector, TC, or STMS	Inspection must only be carried out with RCA approval and may be subject to RCA conditions (eg locations, times). Spotter required – minimum two person activity: • Working under the approved TMP, following the STMS' briefing • Onsite control must be by an STMS L2/3 or an STMS- NP(CAT B or C) Inspection not permitted.	level of TTM with appropriately warranted staff
Level 3 (Any speed)		Must use a higher level of TTM with appropriately warranted staff	

Important elucidation

* Inspector will not be qualified to design or submit traffic management plans

This submission is applying to still allow the TC inspector to conduct inspection activities on the level 3 (Category C) Roads (with minor adjustments outlined), however the generic TMP submission will not include level 3 (Category C) Roads or inspections on State Highways. These roads are to be treated with a site specific TMP in accordance with the RCA, NOC Representative or District Council RCA guidelines.



Appendix

Sample Standard Operating Procedure: Survey and Inspection for TTM Engagement-Approvals and Implementation.

Sample Survey and Inspection Generic Proforma

Sample Engineering Exception Decision: Surveying within the carriageway on Level LV and Level 1 Roads

Sample Survey and Inspection Traffic Management Diagrams

Sample Survey and Inspection Checking Process for Generic Checking Process for Generic TMPs Incorporating Onsite Record Form

A GUIDE TO STANDARD OPERATING PROCEDURE

ROADSIDE SURVEYS & INSPECTIONS

Description of Activity

Carryout surveying and inspections in the legal road corridor.

Task	Date from activity	Operating procedure	Person Responsible
1	Monthly	Monthly toolbox type briefing my qualified person to update the works on any additional requirement, industry updates or to teach new employees how to correctly use the TMP and onsite paperwork	Qualified Manager/ STMS
2	25 - 15 working days before (regional dependent)	 Standard Operating Procedure for Surveys and Inspections Document (this document) referenced and implemented. The manager of activities or operation manager who holds a STMS qualification should check all survey sites against the <i>Proposed GTMP</i> and its associated TMDs to determine: 1. That the site to be surveyed is covered under the approved Generic TMP and associated diagrams or, 2. the level of TTM required can be carried out inhouse by <i>TCi</i> or, 3. The site TTM is too complex and requires outsourcing to a TTM company or, 4. The site setup is not covered under the Generic TMP and requires a Site Specific TMP to be created and approved by the RCA. 	Designated site supervisor
3	48 hrs before	Each RCA have their own requirements around notification of generic TMPs. This is often completed retrospectively at month end. Methods of notification: Notify work start date via <u>https://www.submitica.co.nz/</u> or Deploy the worksite in <u>www.myworksites.co.nz</u>	Designated site supervisor
4	On the day pre-site visit	 The person in control of the site (either STMS, TC or TCi) needs to check that; 1. the TMP has been approved 2. the dates and times 3. the TMDs are fit for intended purpose 	Designated site supervisor

		4. all PPE requirements are met	
		5. all TTM apparatus required is available and in working order and acceptable condition	
5	On the day before arriving or on the site	If reasonable and practical a drive-by of the site should be performed to ascertain the approx. location of work for the day. The designated site supervisor should carry-out a site induction briefing to cover: 1. If TTM diagrams are fit for purpose. 2. Site hazards 3. Hazard mitigations 4. Parking requirements at each site 5. Entry and exiting procedures if applicable 6. Safety zones and no-go areas 7. PPE requirements 8. Unacceptable behaviors IF SITE REQUIREMENTS ARE NOT COVERED UNDER THE APPROVED TMP THE SURVEY ACTIVITY	Designated site supervisor
		SHOULD BE CANCELLED AND REASSESSED	
6	On the day onsite	 Onsite requirements The designated site supervisor implements the static, mobile or inspection requirements to establish the designated TTM on site. Surveyors or other visitors are migrated safely onto site. The survey/Inspection is then carried out. Surveyors or other visitors are migrated off site safely. The designated site supervisor implements the static, mobile or inspection requirements to dis-establish the designated TTM on site. All paperwork including the inspections site checking form is completed for thesite. The site is vacated safely. If this is the last site go to SOP No#7 If another site needs to be visited go to SOP No# 5 until all sites are completed. 	Designated site supervisor
7	On the day post site visit	Return to office and complete any paperwork. TMP and onsite record forms will need to be archived for 12 months. Work completion notification for GTMPs vary depending on the RCA. Please check with your local RCA what their preference is.	Manager/STMS
		Closure out the worksite in <u>www.myworksites.co.nz</u>	



Section I – X Guidelines for Standard TMP for Land Surveying

Inspections and other short-term activities carried out for Land Surveying purposes.

June 2020



Group Name: Survey and Spatial New Zealand

Contributing Organisations: Consulting Surveyors New Zealand and Land Information New Zealand



Standard TMP for Land Surveying

Introduction

This standard TMP for the Surveying Industry has been developed by Survey + Spatial New Zealand in conjunction with Consulting Surveyors New Zealand and Land Information New Zealand

It covers the various types of activities undertaken by surveyors and provides guidance around what CoPTTM measures to apply when working within the road corridor.

Using this Standard TMP

Take the following steps to use this standard plan:

- download the standard TMP
- complete the content with pertinent particulars where indicated by orange writing with (add relevant dates for the year of operation)
- submit the TMP to the road controlling authority for approval (resubmit every year for approval)
- Use the information in the proforma and appendix of this document to ensure that the operation is covered by the TMP
- carry the approved TMP while completing the work
- Complete the inspection on-site record
- retain approved TMP and onsite paperwork for one year after expiry

Updates to this Standard TMP

GTMP, EED and TMP documents associated with this proposal will be subject to updates based on:

- I. Legislative and regulatory changes,
- II. Adapting industry based best practise
- III. Annual health and safety reviews undertaken by the principle



TRAFFIC MANAGEMENT PLAN (TMP) – FULL FORM

Use this form for complex activities. Refer to the NZ Transport Agency's Traffic control devices manual, part 8 Code of practice for temporary traffic management (CoPTTM), section E, appendix A for a guide on how to complete each field.

Organisations	TMP reference:Contractor (Working space):Add the RCA's and contractor's referenceState the name of the contractor responsible for the working space		Principal (Client): State the name of the principal or client for this project (eg NZTA or Chorus)		
/TMP reference	number	Contractor (TTM): State the name of the contractor responsible for the TTM	RCA: State the name of the RCA who controls the road that the worksite will be on. Note: There can be more than one RCA.		
	Road names and suburb		House no./RPs (from and to)	Road level	Permanent speed
Location details and road characteristics		name/s and any affected o include the suburb	Enter house numbers, route positions or power pole numbers where applicable	Enter RCA designation	Enter highest permanent limit
	Keep adding rows visited as sites un	s below for any roads that will be der this approval	As above	As above	As above
	AADT Include AADT where available. The RCA or engineer must provide this information if		Peak flows		
Traffic details (main route)			Include peak hour and heavy vehicle counts where available.		
(available.		The RCA or engineer must provide this information if available.		



Description of work activity

Exclusions:

- Work within the boundary of a state-highway or any Level 3-road corridor is not covered by this TMP. Many RCAs, NOC Representatives or District Council RCAs require site specific TMPs for inspections on a State Highway.
- Work which blocks driveways, restricted parking, loading zones, taxi stands, closures that require footpath diversions towards live lane or cycle lane closures/diversions.
- Setups not covered by the generic TMDs attached

Surveying operations summary

Includes land, location-based spatial information, construction, resource management and housing, cadastral, engineering, hydrographic, geodetic surveying, land development and urban design.

The two main categories of survey process are:

- either measuring to something that already exists, such as an existing survey mark, or a feature, or
- setting out the position of something, such as a boundary mark, or something to be constructed.

Work Activity Period:

30 secs to a maximum of 6 hours.

Working Space Dimensions not including safety zones:

3m²

Plant, equipment, and personnel required:

Plant:

One utility vehicle (Light Car, Ute or Van)

Equipment:

Light weight, frangible surveying equipment which is generally either:

- on tripod legs, such as a GPS base station, a total station, or a scanner
- on a pole, such as a GPS rover, or a reflective prism for use with a total station
- handheld, such as a tape measure, a handheld GPS or a mobile scanner

Personnel:

1 to 2 persons

RCA consent (eg CAR/WAP) and/or RCA contract reference

Add RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.

Activity required	Access to live lane required?	Level of Road	TMD
	Locating or observing mark or feature outside of carriage way NOT ENTERING THE LIVE LANE (No time restriction)	Low Volume Level 1 Level 2 Level 3 roads not covered in this TMP	Sheet 1
Working on Footpaths and Berms			Sheet 2
(No time restriction)	Locating or observing mark or feature in the live lane ENTERING THE LIVE LANE	Low Volume Level 1 Level 2 Not permitted on Level 3 roads	Sheet 2
	(Up to 5min in the lane)		
Working in a marked/inferred shoulder or in a parking lane.	Locating or observing mark or feature outside of carriage way NOT ENTERING THE LIVE LANE (No time restriction)	Low Volume	Sheet 3 Sheet 4
Including Tripod Straddling the kerb and Channel	Locating or observing mark or feature in the live lane ENTERING THE LIVE LANE (Up to 5min in the lane)	Level 1 Level 2LS Not permitted on Level 3 roads	Sheet 5 Sheet 6
	Locating or observing mark or feature		Sheet 7
Working where there is no edge line or inferred edge line.	outside of carriage way NOT ENTERING THE LIVE LANE (No time restriction)	Low Volume	Sheet 8
Including Tripod Straddling the kerb and Channel Overtaking vehicles not crossing centreline or entering flush median	Locating or observing mark or feature in the live lane ENTERING THE LIVE LANE	Level 1 Level 2LS Not permitted on Level 3 roads	Sheet 9 Sheet 10
	(Up to 5min in the lane)		
Working in the lane on a short no exit road – over 10mins	ENTERING THE LIVE LANE (No time restriction)	Low Volume only	Sheet 11
Working in the lane	ENTERING THE LIVE LANE (Up to 10min in the lane)	Low Volume Level 1	Sheet 12
Pedestrian detour away from the carriageway	Locating or observing mark or feature Blocking the footpath	Low Volume Level 1	Sheet 13
Pedestrian Detour in to the front berm		Level 2	Sheet 14

Planned work programme							
Start date	Enter earliest date activity may start	Time	Enter earliest time activity may start	End date	Enter latest date activity may finish allowing for unforeseen issues	Time	Enter latest time activity may finish allowing for unforeseen issues
Consider significant	Working hours	•					
stages, for example:	Road level	Operatior	ı			Working	window
1. road closures	Low Volume	No restric	tions for Low Vol	ume roads			
2. detours	Level 1 & 2 Surveyor does not need to enter the carriageway No restrictions					tions	
no activity periods.	Level 1 & 2	Surveyor needs to enter the carriage way 0700 – 1900				900	

				ence, for example the corridor acco permit (WAP) and/or any RCA contr			
	Preliminary	Procedures					
	It is assumed	ssumed that the designated site supervisor will have followed the steps in the SOP guide attached to the correct level of TTM required for the location as well as the correct diagram for the activity.					
	 A toolbo Revisit 1 inspect a systems 	Revisit TTM requirements and approved TMD					
		tages is the order of establishment of we lian, traffic islands and lane for su		ated in the road corridor includin	g berm,		
	If the area	at the site and park at appropriate a where the vehicle will be parking one into this area, then the following	g is not usually us	ed for parking or vehicles do not			
		 Prior to arriving at site and in required for your operation as w vehicle. 	n a nearby safe lo	cation, install the vehicle mounter			
		e the positions of the survey mark , footpath, or berm of roads.	s that are needed	for the survey. Typically, they w	ill be in the		
	chis	If marks are under seal or dug into the berm, expose the survey marks by digging out with spade or chisel and hammer. If the marks are in the live lane and are under seal a Mobile closure will be required with the appropriate TTM vehicles					
		and cone off the Tripod on the exception of the exception of the exception of the second of the seco	xposed mark. May	v have spotter next to the total st	ation. This		
	5. Place	survey marks for where the total	station will need to	be moved next.			
		ve all necessary survey marks i.e ance and bearing (typically taking			ecord the		
	7. Observe all the features required to complete the survey (for example kerb lines, edge of seal, footpath, face of buildings, manholes). This requires walking to those points with a pole and prism and record the distance and bearing (typically taking no longer than 30 seconds). If spots are inaccessible (e.g. building ridges, centrelines of roads, and gutters) measure distances and bearings via reflectorless means.						
	 Once all features are observed and recorded, the Tri-pod is moved to the next survey mark. The process then repeats from point 5-7. The average total station set up is roughly 20 minutes to 30 minutes. 						
	set	 This process is repeated until the survey is complete. This can range from 1 - 50 set ups. Typically, 8 set ups per day and can cover various roads. 					
	-	ear is packed up and the survey i					
	11. Vehicle mounted signs to be removed before leaving site or if 1a. was followed - Once the vehicle has left site, the vehicle mounted signs and amber flashing beacon can be removed in a nearby safe stopping area.						
Alternative dates if activity delayed							
Road aspects affected	d (delete either	Yes or No to show which aspects	are affected)				
Pedestrians affected?	Yes	Property access affected?	No	Traffic lanes affected?	No		
Cyclists affected?	No	Restricted parking affected?	No	Delays or queuing likely?	No		



AGENCY	
Proposed traffic mana	agement methods
	Installation procedures When there is no static TTM equipment required within the carriageway 1. Drive past the site location for an initial site check 2. Arrive at the site and park at appropriate location (in driveway if allowed, in public parking if available) 3. If the area where the vehicle will be parking is not usually used for parking or vehicles do not often pull off the live lane into this area, then the following but be abided by: 3a. Prior to arriving at site and in a nearby safe location, install the vehicle mounted signage required for your operation as well as an amber flashing beacon, if not already fixed to the vehicle. The following table sets out the best practice to stop at the intended inspection site when following 3a.
	When you approach to stop at the intended inspection site
	ALWAYS • Enter to the left
	BEACON • Turn the beacon on when approaching the site INDICATE • Indicate your intentions for minimum of 3 seconds, check traffic behaviour behind you, slow down and drive into the site • When in the site ensure the vehicle is parked at least 2 metres away from the live
	PARK SAFELY PARK SAFELY PARK SAFELY PARK SAFELY PARK SAFELY PARKING REQUIREMENTS leave your beacon on
	 EXITING VEHICLE Check your mirrors for approaching traffic and ensure it is safe to exit the vehicle before opening your door Make sure you are wearing your high visibility clothing. Keep an eye on approaching vehicles at all times
(includes parking of plant and materials storage)	 Work vehicle to provide protection when installing static signage and delineation devices within the carriage way, then It can be moved in to position within the working space if required. An amber flashing beacon, visible from all angles, must be on during installation, maintenance and removal.
	 Access equipment from the non-traffic side of the vehicle When working in the carriageway, surveyor must work in front of their vehicle. Their work vehicle will
	provide advanced warning and protection.
	Any Static signage that needs to be install must be installed via the footpath and walked out.
	• If there is no footpath then the work vehicle must be parked 10m in advance of the surveyor while they install the sign on foot in front of the work vehicle. Vehicle must have vehicle mounted sign and amber flashing beacons during this procedure and following the steps below;
	 The first sign installed must be the advanced warning sign on the side where the work will be carried out and then end of works signage installed on same side of road including any side streets,
	 vehicle completes a loop on a single direction carriageway or performs a safe turn on a bidirectional road to install advanced warning, direction and protection and end of works signs on opposite side of the road,
	3. once all signs have been installed, delineation devices that form the taper or lateral exclusion zones may be installed.
	Drive through and site check procedures
	Prior to personnel, vehicle, equipment set-up on site, a drive through check must be performed by the Site Supervisor to ensure the site has been set up as per the selected TMDs, this should include the checking of worksite layout distances as per CoPTTM dimension tables attached to this TMP.
	The Onsite Record form should be completed to record the establishment details for the site.



Parking Requirements

Vehicles shall be parked in any space that is ordinarily allowed with in the carriageway (including, a kerb line absent of broken yellow lines, shoulders, parking lanes, marked car parking spaces and side roads).

Where this is not reasonably practical, a work vehicle (necessary for the carrying out of the non-invasive work) may be parked on the berm provided the berm is not damaged in doing this and where parking is not specifically prohibited by signs / formal resolution.

It is not permitted to park in any marked cycle lane, with or without broken yellow lines.

	<u></u>	ootpath requirements
Location	Minimum width	Comments
Residential/Rural /Suburban centre	1.2m	An existing footpath width may be used when it is narrower than the
Central business district (CBD) and commercial zones.	2.0m	when it is narrower than the minimums shown. Where the length of the temporary
Commercial zones include shops, schools, aged persons homes or facilities, hospitals, tourist attractions, bus stops, libraries.		footpath exceeds 20m a pedestrian passing bay may be required.

Where the activity impacts a footpath and minimum footpath widths cannot be maintained, alternative routes with a firm smooth surface and no trip hazards are to be provided in the following order of preference:

1. onside of road reserve away from the carriageway

2. between the working space and carriageway (but not into the live lane)

Other options under CoPTTM are not available in this TMP a higher level of TTM and Qualification are required.

	Cycle Lane Requirements					
Type of lane	Speed	Minimum Width (m)				
Single direction cycle lane	Speed limit does not exceed 50km/h	1.0m *				
Single direction cycle lane	Speed limit exceeds 50km/h	1.5m				
Two-way cycle lane	Any speed	2.0m				
Shared footpath and cycle way	Any speed	2.2m #				

***Note:** A minimum lane width of 1.5m is required if the temporary cycle lane is uphill as riders tend to pump their cycles from side to side as they climb the hill.

It is not permitted to park in any marked cycle lane, with or without broken yellow lines.

	Working space population
Attended (day)	 If work vehicle is parked in a regular parking space as detailed above and the inspector is not accessing the live lane, beacon and hazards may be turned off.
	 Amber flashing beacons shall be utilized on all vehicles entering the worksite along with vehicle indicators. Once inside a static working space all beacons shell be turned off and vehicle hazard lights initiated
	Tripods placed on the footpath, kerb, shoulder, parking space need to have cones to delineate each leg
	Instructions for Inspection Activities when Entering the Live Lane 1. Surveyors must move from live lanes to avoid traffic. They must not expect traffic to drive slowly or drive around them

WAKA KOTA NZ TRANSPORT AGENCY	AHI RCA consent (eg CAR/WAP) and/or RCA contract reference Add RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.					
	 On level LV, level 1 & 2 roads, the person completing the inspection cannot be on a live lane for more than 5 minutes Unless otherwise approved by the RCA, all inspections on the live lane of level 1 & 2 roads require 					
	a spotter . The RCA may provide a list of roads, times and/or activities suitable for inspection by a single inspector					
	4. There must be CSD to the surveyor when on the live lane. If this cannot be achieved, a spotter must be placed in a position where CSD can be attained and verbal instructions be given to the surveyor. It this is not possible, a static or mobile operation is required.					
	 5. A spotter is not required for inspections on level LV roads or working off the live lane of a level 1 & 2 road 					
	6. An unaccompanied inspector may walk across a level LV, level 1 & 2 road					
	 A vehicle is not required on a level LV or level 1 road with a permanent speed of less than 65km/h if the inspector remains on a footpath 					
	All site checks and or changes to be recorded on the "on site record"					
Attended (night)	No Inspection will be undertaken at night under this TMP					
Unattended (day) / (night)	No Inspection will be undertaken as unattended sites under this TMP					
Detour route	No is required with the operation required under this TMP					
	Pre-removal procedures					
	 Identify any site-specific issues to be addressed regarding disestablishment of the site, document them and make notes on the GTMP if required, 					
	 Confirm that the closure area/working space has been safely cleared of all non TTM personnel 					
	and, equipment.					
	When no static TTM equipment was required with in the carriageway					
	1. And the work vehicle is parked in a regular parking space as detailed above, simply obey the road code rules for re-joining traffic flow from the side of the road.					
	1a. Otherwise, initiate the process below to rejoin traffic.					
	When you are leaving the inspection site					
	BEACON • Leave the beacon on					
	INDICATE • Indicate your intentions for minimum of 3 seconds					
	MIRRORS • Check your mirrors for a safe gap in the traffic					
	Applorate and marge apply into the traffic lane. Keen an even on traffic behavior					
	ACCELERATE ACCElerate and merge salely into the trainc lane. Reep an eye on trainc behavior a all times					
Removal	BEACON • Turn the beacon and indicator off when you have reached normal operating speed					
	When static TTM equipment was required with in the carriageway (TMDs XX – XX)					
	Removal procedure					
	Operations to remove TTM signs and devices to disestablish a static site shall be performed in this order:					
	 Remove all delineation devices and pedestrian management signs first, be that on the footpath or in the shoulder. This should be with the work vehicle parked 10m in advance of the surveyor collecting the delineation devices. 					
	2. end of works signage shall be removed from each side of the road including any side streets, all advanced warning signage will be left in place and collected last					
	3. a drive through check shall be performed by the STMS or delegated TC or TCI to ensure the site has been completely disestablished					
	4. One the vehicle has left site, the vehicle mounted signs and amber flashing beacon can be removed in a nearby safe stopping area.					
	The Onsite Record form should be completed to record the disestablishment details for the site.					
	Edition 4 April 200					



Proposed TSLs (see TSL decision matrix for guidance)						
	TSL details as required Approval of Temporary Speed Limits (TSL) are in terms of Section 6 of Land Transport Rule: Setting of Speed Limits 2017, Rule 54001/2017 (List speed, length and location)	Times (From and to)	Dates (Start and finish)	Diagram ref. no.s (Layout drawings or traffic management diagrams)		
Attended day/night	TSL are not included and are not authorised under this TMP					
Unattended day/night	TSL are not included and are not authorised under this TMP					
TSL duration	Will the TSL be required for longer than 12 months? If yes, attach the completed checklist from section I-18: G for TSLs to this TMP.	Nonitoring Processes	No			

Positive traffic management measures

TCi Site Supervisor will maintain footpath widths, cycle lane widths and park legally at all times. As there are no TMDs that incorporate TSLs as part of this approved GTMP document the use of positive traffic management is not applicable.

Contingency plans		
Generic contingencies for: • major incidents • incidents • pre planed detours.	 Major Incident A major incident is described as: Fatality or notifiable injury - real or potential Significant property damage, or Emergency services (police, fire, etc) require access or control of the site. 	 Actions The TCi site supervisor must immediately conduct the following: stop all activity secure the site to prevent (further) injury or damage contact the appropriate emergency authorities render first aid if competent and able to do so notify the RCA representative and / or the engineer under the guidance of the officer in charge of the site, reduce effects of TTM on the road or remove the activity if safe to do so re-establish TTM when advised by emergency authorities that it is safe to do so Comply with any obligation to notify WorkSafe.

WAKA KOT		CA consent reference, for example the or or work access permit (WAP) and/or an	
	Incident	Actions	
	An incident is described as:	The TCi site supervisor must	immediately conduct the
	 minor or non-inquiry accident that has t potential to affect traffic flow 	following: • stop all activity and tr required	affic movement if
	 structural failure of the road. 	 secure the site to pre injury or further data 	
		 notify the RCA representation of the representation o	sentative and / or the
		 TCi site supervisor to safely remove TTM traffic flow if safe to 	I and to establish normal
			d traffic movements when Ind when traffic volumes
	Detour	Actions	
	Detour not applicable for operations covered by TMP	is Detour not applicable for ope TMP	rations covered by this
	Note also the requirements for no interferer	at an accident scene:	
	In the event of an accident involving serious ha equipment, is removed or disturbed and any wi except to:		
	4. save a life of, prevent harm to or relieve	ne suffering of any person, or	
	5. make the site safe or to minimise the ri	of a further accident; or	
	6. maintain the access of the general pub	to an essential service or utility, or	
	7. prevent serious damage to or serious lo	of property, or	
	8. follow the direction of a constable acting	n his or her duties or act with the peri	mission of an inspector.
Other contingencies to be identified by the applicant	The TCi Site Supervisor will assess, order wo space safely, followed by the disestablishmer following circumstances.		
(i.e. steel plates to quickly cover excavations)	 The work cannot be carried out safely en road users. (HSAW Act) 		-
	There is a condition that would require the more than 5mins)	e of a higher level of TTM (e.g. acc	ess the live lane for
Authorisations			
	Will controlled street parking be affected?	No Has approval been gran	ted? N/R
Parking	Any planned work:		
restriction(s)	1. which requires the reservation of parki	spaces,	
alteration authority	2 which affects a paid parking, disability,	served, loading or any other service.	zone,
	will require additional authorization from the The authorization process and duration may		

WAKA KOTA NZ TRANSPORT AGENCY		onsent (eg C RCA contra			sent reference, for example the corridor acce access permit (WAP) and/or any RCA contra		
	hazards onsi	te.					
Authorisation to work at permanent	Will portable permanent tr	-	s be used or be changed?	No	Has approval been granted?	N/R	
traffic signal sites							
Road closure authorisation(s)	Will full carri more than 5 stipulated tin	minutes (or o	ure continue for other RCA	No	Has approval been granted?	N/R	
Bus stop relocation(s) –	Will bus stop activity?	l bus stop(s) be obstructed by the ivity?			Has approval been granted?	N/R	
closure(s)							
Authorisation to use portable traffic		Make, model and Not Required					
signals	NZTA compli	ant?	Not Required				
EED							
Is an EED applicable?	Yes		EED attached?	Yes			
Delay calculations/tria	al plan to dete	rmine potenti	ial extent of delay	s			
No delay calculation red	quired as no op	eration under	this TMP reduce tr	affic capac	ity		
Public notification pla	n						
Public notification requi	rements to be	set out by eac	h RCA if required for	or this TMF)		
Public notification pla	in attached?	No					

On-site monitoring plan

Attended (day)	If static equipment is installed for longer than 2 hours, this will be visually checked at least every 2 hours and recorded on the onsite record by the site supervisor.
Unattended (day and/or night)	Not included in this TMP

Method for recording daily site TTM activity (eg CoPTTM on-site record)

A custom on-site monitoring record has been designed to cover aspects of both the NZTA CoPTTM On-site record as well as the Generic TMD checking form.

As these sites are often be visited for such a short period of time the standard form for full static closure was not fit for purpose.

An inspection shall be made after TTM installation and recorded in 2 hourly site checks on the CoPTTM onsite record form.

Additional site details may also be recorded on:

- Custom Onsite record form
- Site supervisor's Diary
- SCR Form
- Induction/Toolbox forms

Site safety measures

PPE requirements are as per RCA minimum requirements and the individual companies internal Policies as listed below: CoPTTM minimum requirement:

• CoPTTM compliant Hi-Viz vest (compulsory),

Additional company policies or risk assessed PPE requirements can be and are not limited to:

Safety Foot ware

WAKA KOT NZ TRANSPORT AGENCY	TAHI	RCA consent (eg CAR/W and/or RCA contract ref		Add RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.		
Safety eye vHard Hat	vear					
 Gloves 						
Temporary safety barrier system	barri	a temporary safety er system be used at vorksite?	No	If yes, has the temporary safety ba been designed by an installation de independently reviewed as being fin purpose?	esigner and	No
	State	ment from temporary safe	ety barrier	rinstallation designer attached	Not required	

Other information

Any planned work: which requires the reservation of parking spaces, which obscures or affects a paid parking, disability, reserved, loading or any other service zone or which requires the relocation of a bus- stop, will require additional authorization from the RCA and TMC to be arranged by the Site Supervisor in charge before the work proceeds, the authorization process and duration may be subject to the need to eliminate hazards onsite.

- All vehicles will be equipped with amber flashing lights
- TCi, TC or STMS onsite is to write up a hazard ID and brief and staff onsite prior to work starting.
- STMS will always wear a compliant TTMCW yellow hi-vis vest/clothing clearly marked with STMS and TCi or TC are to wear Orange Hi-Vis vest.
- All staff/contractors are to comply with the principal clients' health and safety procedures and/or the contractors' health and safety procedures.

Sign Name	Sign Reference	Illustration	Requirements for use
ROAD	TV3	ROAD INSPECTION	This sign must be used in conjunction with vehicle-mounted flashing amber beacons and must be mounted on the rear of any vehicle conducting road inspections.
INSPECTION	100		Surveyor will use this sign when their vehicle is acting as the advanced warning for their operation (e.g. there is no static advance warning sign erected).
PASS WITH CARE	TV4 AND RD6L	PASS WITH CARE	This sign advises road users to take care whilst passing. It is mounted on the rear of shadow and work vehicles involved in temporary mobile operations.
	TV4 AND RD6R		The RD6L or RD6R sign may be omitted when the vehicle is fitted with an arrow board.
	TV4	PASS WITH CARE	Where a vehicle in a mobile operation is constantly changing position in the lane and it is impractical to frequently change the RD6L/R sign, this component may be omitted.
			Surveyors will use this when their vehicle is providing protections for their operation (e.g. There is a static advanced warning erected)
	Approve	ed static signs that su	rveyors can use under this TMP
Sign Name	Sign Reference	Illustration	Requirements for use

Approved vehicle mounted signs that surveyors can use under this TMP

		(eg CAR/WAP) ontract reference	Add RCA consent reference, for example the corridor access request (CAR) or work access permit (WAP) and/or any RCA contract reference.
Road works LevelsLV and 1	T1A		This sign is erected at all attended worksites. The sign is also used at unattended worksites where there are hazards within 5m of the edgeline. An authorised supplementary sign may be used.
Road works SURVEYING	T139	SURVEYING	This supplementary plate must be displayed when a survey party is on the roadway or within 5m of the edgeline. It can be used in conjunction with a T1A advance warning sign.
WORKS END	TG2	WORKS END	This sign is used to indicate the end of a worksite that has T1 type advance warning signs.
	TU31	★ ★	These signs are used to guide pedestrians to a temporary route or formal crossing point, and indicate the alignment of the temporary route, when the normal facility is not useable due to road works or some other temporary activity
	TU32	* →	
PEDESTRIAN DIRECTION	TU33	下次	
	TU34	* *	
·	TU35	↑ Ż	
·	TU36	* *	
	hnical-note-Level-2-low-s		https://www.nzta.govt.nz/assets/resources/code-temp-traffic-
Level	AADT Guidelines	Commen	ts
Level 2 low speed	>15,000vpd	<65km/h May have	a central median division with at grade access
1.2. The numbers on t	this table are indicative a	Ind not compulsory. F	CAs may retain the road at the existing level.
•	the use of level 1 signs of		
	-lane roads Gated signs	s not required	
4. Working on berm or		lden electric de la c	
parking/specia			LV and level 1 roads to be used on 2LS roads including
	nanual part 8 CoPTTM		A: Traffic management plans Edition 4, April 2020



6.1. Only the work vehicle will be required when TTM set out is outside the edgeline. No shadow vehicle will be required when the work vehicle can park legally.

6.2. Once the signs/cones for the worksite have been unloaded to the side of the road and the advance warning sign has been installed the work vehicle may act as a shadow vehicle while the taper is being installed.

Site specific layout di	agrams								
Number	Title								
Enter applicant diagram number.									
Also consider whether a layout diagram is required for set-up /removal of the worksite.	Enter name of attached diagram	Enter name of attached diagram							
As above	As above - Enter all TMD they ne	eed to be use	d or might be n	eeded as a c	ontingency				
As above	As above								
As above	As above								
Contact details									
	Name		24/7 contact number	CoPTTM ID	Qualification	Expiry date			
Principal	Organisation named on permit	Organisation named on permit			Optional	Optional			
ТМС	Name		24/7 contact number	Optional	Optional	Optional			
Engineers' representative		Detail optional - Independent person employed by engineer whose responsibilities include TTM			Optional	Optional			
Contractor	State name of the contracting com the name of their contact person	State name of the contracting company and the name of their contact person			Optional	Optional			
STMS	Name Where multiple names are include TMP, the name of the STMS in ch be written on the On-site record		24/7 contact number	CoPTTM ID number	Level of qualification	Date of expiry			
тс	Name		24/7 contact number	CoPTTM ID number	Level of qualification	Date of expiry			
Others as required	Name		24/7 contact number	Optional	Optional	Optional			
TMP preparation									
	Elise Freeman	22/05/2020	Esterneme	60475	2-3 STMS P	09/04/2021			
Preparation	Name (STMS qualified)	Date	Signature	ID no.	Qualification	Expiry date			
This TMP meets CoP	TTM requirements		Number of	diagrams atta	ched				
TMP returned for									
correction (if required)	Name	Date	Signature	ID no.	Qualification	Expiry date			



Engineer/TMC to co	Engineer/TMC to complete following section when approval or acceptance required								
Temporary safety barrier system	The attached temporary road safety barrier design has been independently reviewed as being fit for purpose Not required								
TMP Approved									
	Name	Date	Signature	ID no.	Qualification	Expiry date			
Acceptance by TMC (only required									
if TMP approved by engineer)	Name	Date	Signature	ID no.	Qualification	Expiry date			
Qualifier for engineer or TMC approval									

Approval of this TMP authorises the use of any regulatory signs included in the TMP or attached traffic management diagrams.

This TMP is approved on the following basis:


- 1. To the best of the approving engineer's/TMC's judgment this TMP conforms to the requirements of CoPTTM.
- 2. This plan is approved on the basis that the activity, the location and the road environment have been correctly represented by the applicant. Any inaccuracy in the portrayal of this information is the responsibility of the applicant.
- 3. The TMP provides so far as is reasonably practicable, a safe and fit for purpose TTM system.
- 4. The STMS for the activity is reminded that it is the STMS's duty to postpone, cancel or modify operations due to the adverse traffic, weather or other conditions that affect the safety of this site.

Notification to TMC prior to occupying worksite/Notification completed

Type of notification	Describe the notification procedure to be used	Notification	LIAIA	Record date notification was completed
to TMC required		completed	IIMA	Record time notification was completed



ENGINEERING	ENGINEERING EXCEPTION DECISION										
Name of RCA	001										
Basic description of the activity associated with EED Occupation of a shoulder area when there is no edge-line or inferred edge-line without the need to remove equipment or personnel from the carriageway on the approach of a vehicle or when the water activity exceeds 5 minutes											
Location detai	Location detail and scheduled dates										
Leastion	This EED rela			De	4	From: 0	1/05/2020				
Location	State the NZT	A NOC or	District Council Region	Da	ates:	To: 30/0)4/2021				
It is proposed to	vary the requ	irements c	of CoPTTM.								
WHAT the prol	olem is: (a) de	escribe the	road environment constraint,	(b) state CoP	PTTM rec	quirement	s for the propos	sed activity.			
a. The road en	vironment co	nstraint	Due to survey points locate activities require the laser with one leg positioned in t	level survey tri	ipod to b						
b. CoPTTM req		r the	All equipment and personr			• •					
proposed ac	tivity		All equipment and personr 5-minute period approved				so as not to ex	ceed the maximum			
WHY CoPTTM	compliant TT	M should	not/cannot be installed.								
presence of an unreasonable	Where there is no edge-line or inferred edge-line, the surveyor is obliged to move off the carriageway with their equipment in the presence of an approaching vehicle or after 5 minutes duration. The activity is constrained by CoPTTM requirements that are unreasonable and not fit for purpose for this type of activity in this region of the carriageway. The contractor is forced to apply TTM treatments that often take longer to setup than the duration of the work and are impracticable based on the mobile nature of the work										
HOW will safet	-										
TV4/T139 sigr	nage will be pa	irked 10m	l edge-line and there is a lega behind the work area. The ve width requirements based on	hicle will be pa	arked on	the lane	or straddling th				
This EED must	be attached	to the TM	P. Any generic EEDs must l	be forwarded	to the N	IZ Transp	port Agency.				
EED – Proposa	al										
Signed for and	Paralla	ixx Ltd									
behalf of:	Insert cor	ntractor's na	ame								
	Elise Fre	eeman		Consultant		604	75	09/04/2021			
	Name			Desigi	nation		ID number	Expiry date			
Signed by:	Emfee	her-				16/	03/2020				
	Signature	;				Dat	te				
EED – Approve	ed by										
Signed for and behalf of:											
	Insert RC	A name									
	Name			Desigi	nation		ID number	Expiry date			
Signed by:	Ivaille			Desigi			10 HUHBU	LAPITY VAIC			
	Signature)				Dat	te				



OPERATION 1 - LR/LV, LOW VOLUME, LEVEL 1, & LEVEL 2 ROADS FOOTPATHS AND BERMS (NOT ENTERING THE LIVE LANE)

CONDITIONS FOR LV AND LEVEL 1 ROADS:

Total operation can be contained to the berm and/or footpath

- Always direct pedestrians away from the carriageway, onto a back berm if available.
- If the footpath is completely block by your equipment and no back berm available, the front berm can be used keeping pedestrians 1m away from the live lane.

TIME RESTRICTIONS:

• None (avoid peak hours before and after school starts).

PERSONNEL REQUIRED:

• Once briefed by an STMS - TC inspector or TC or STMS can carry out this operation - no spotter required.

VEHICLE (ADVANCED WARNING):


• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. sign selection to be an advanced warning sign TV3 "ROAD INSPECTION."

	OR	RIGINAL IN COLOUR							
-11	Rev	Denciption	ம் கை	d Date	DRAWING ORIGINATOR:	ORIGINAL SCALE:		PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
1	1	INITIAL DRAWING	A.G. D.L	. 22/05/20			Antonette Galang (Level 2/3 NP, #129806, 10/01/2022)		
					PARALLA X	NITC	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV/L1/L2 SURVE
						N.I.S	This drawing, the design and concept remain the property of	CONSULTING SURVEYORS NEW ZEALAND	🛛 OPERATION 1 – FOOTI
1					Parallaxx Limited Telephone: 0800 333 772		Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the		
					PO Box 302473 Web: www.parallaxx.co.nz North Harbour 0751 Email: info@parallaxx.co.nz		associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		(NOT ENTERING TH
Q			1	1			and the second s		

EYING GENERICS TPATHS AND BERMS THE LIVE LANE)

PXJ-9410								
SHEET NO:								
Sheet	1	Of	14					

DRAWING TITLE-



OPERATION 2 - LR/LV, LOW VOLUME, LEVEL 1, & LEVEL 2 ROADS FOOTPATHS AND BERMS (ENTERING THE LIVE LANE)

CONDITIONS FOR LV ROADS:

- Surveyor can access the live lane for a maximum of 5 min. with rover pole or other light handheld equipment (excludes tripod).
- Multiple entries to the lane permitted throughout the day, avoid peak hour traffic.
- Once surveyor steps into the lane CSD must be available to them for approaching road users. If csd can not be achieved a spotter will be required.
- Surveyor must leave the road when traffic is approaching, they must not expect traffic to slow down or avoid them.

TIME RESTRICTIONS:

• Maximum 5 mins. once surveyor enters the lane (avoid peak hours before and after school starts as well as peak traffic flows)

PERSONNEL REQUIRED:

 Once briefed by an STMS – TC Inspector or TC or STMS can carry out this operation – no spotter required

VEHICLE (ADVANCED WARNING):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. sign selection to be an advanced warning sign TV3 "ROAD INSPECTION."

CONDITIONS FOR LEVEL 1 ROADS:

• Apply all other notes above.

PERSONNEL REQUIRED:


 Once briefed by an STMS – TC Inspector OR TC or STMS can carry out this operation – Spotter required when entering the live lane.

												_
	DRAWING TITLE:	INTRACT:	PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRA	DRAWN & CHECKED BY: Antonette Galang (Level 2/3 NP, #129806,	ORIGINAL SCALE	, ,	DRAWING ORIGINATOR:	Date	Child	கு	Devaciption	Rev
R/LV/L1/L2 SURVEYI	Пір			10/01/2022)				22/05/20	. D.L.	A.G	INITIAL DRAWING	1
VLV/LI/LZ SURVEI				Diana Lising (Level 2/3 NP, #110586, 20/08/2022)	MITC		I DARAL					
ration 2 – footp	II OPER	S NEW ZEALAND	CONSULTING SURVEYORS I	This drawing, the design and concept remain the property of Parallaxx Limited	N.I.S	IAM	1 - 7 AEXZ AL		\square			
	••• •••		5 6 1	Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the crossing Traffic Management Plus) much be utilized and the the second		Telephone: 0800 333 772	Parallaxx Limited		\square			
(ENTERING THE L	JI	J		the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		Web: www.parallaxx.co.nz Email: info@parallaxx.co.nz	PO Box 302473 North Harbour 0751					
	ا					Email: info@parallaxx.co.nz	North Harbour 0751					L

EYING GENERICS TPATHS AND BERMS e live lane)

XJ-8	9410	
2	of	14
	xJ-9	XJ-9410 2 of

DRAWING TITLE:



OPERATION 3 - LR/LV, & LOW VOLUME ROADS WORKING IN A SHOULDER OR PARKING LANE (NOT ENTERING THE LIVE LANE)

CONDITIONS FOR LV ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required


VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. If there is CSD to the work vehicle then select the Advanced Warning sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

Rev	Description	цў.	Child	Date	DRAWING ORIGINATOR:	ORIGINAL SCALE:	DRAWN & CHECKED BY: Antonette Galang (Level 2/3 NP, #129806,	PREPARED FOR CLENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
1	INITIAL DRAWING	A.G.	D.L.	22/05/20	PARALI A 🗙	NIS	Antonette Catalang (Level 2/3 NP, #129906, 10/01/2022) Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV SURVEYIN
					Parallaxx Limited Telephone: 0800 333 772	N.I.J	This drawing, the design and concept remain the property of Parallaxx Limited. Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 3 - SHOULD
F					PO Box 302473 Web: www.parallaxx.co.nz North Harbour 0751 Email: info@parallaxx.co.nz		associated Traffic Management Plan just be utilised only at the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		(NOT ENTERING TH

Iane/Shoulder, keeping a es. he working space; Surveyor ole. back of the work vehicle le otherwise static signage legally parked. hours where possible). hours where possible). hours where possible). Inspector or TC or STMS to spotter required DIRECTION AND PROTECTION): orked with beacons on and dertaking the operation. If then select the Advanced ON." If static signs are t TV2 "Pass With Care" for

	DRAWING TITLE:
TING GENERICS	PXJ-9410
DER OR PARKING LANE	SHEET NO:
THE LIVE LANE)	Sheet 3 of 14



OPERATION 4 - LEVEL 1 & LEVEL 2LS ROADS WORKING IN A SHOULDER OR PARKING LANE (NOT ENTERING THE LIVE LANE)

CONDITIONS FOR L2LS ROADS:

- There must be CSD to the work vehicle on Level 2LS roads.
- Special RCA approval can be obtained to use Level 1 static signage on Level 2LS roads if CSD is not achievable.

CONDITIONS FOR L1 ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required


VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. If there is CSD to the work vehicle then select the Advanced Warning sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

EXTRA SAFETY DEVICES:

• A 10m taper must be installed, with a longitudinal safety zone as per distance layout table attached, the work vehicle MUST be included in the working space and a 1m lateral safety zone maintained around the working space, cones to delineate the length of the working space. Apply all other notes above.

5														
æ	•	Denception	ு கை	d Date	DRAWING ORIGINATOR:		ORIGINAL SCALE:	DRAWN & CHECKED BY:	PREPARED FOR CLENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:	DRAWING TITLE	-		
F	1	INITIAL DRAWING	A.G. D.L.	22/05/20		w I	NITO	Antonette Galang (Level 2/3 NP, #129806, 10/01/2022) Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		L1 & L2LS SURVEYING GENERICS	P>	XJ-94	410	
E					FARALI A	∖	N.I.S	This drawing, the design and concept remain the property of Parallaxx Limited.	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 4 - SHOULDER OR PARKING LANE	SHEET NO:			
ŀ	+		++		PO Box 302473 V	Telephone: 0800 333 772 Web: www.parallaxx.co.nz Email: info@parallaxx.co.nz		prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approving from the approving engineer and/or road controlling authority.		(NOT ENTERING THE LIVE LANE)	Sheet	4	of 1	4∥



OPERATION 5 - LR/LV, & LOW VOLUME ROADS WORKING IN A SHOULDER OR PARKING LANE (ENTERING THE LIVE LANE)

CONDITIONS FOR LV ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required


VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. If there is CSD to the work vehicle then select the Advanced Warning sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

	O	RIGINAL IN COLOUR									
1	Rev	Description	ц,	Child	Date	DRAWING ORIGINATOR:	J	ORIGINAL SCALE:	DRAWN & CHECKED BY: Antonette Galang (Level 2/3 NP. #129806.	PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G.	D.L.	22/05/20		AX	NITC	Antonette Galang (Level 2/3 NP, #129906, 100/12022) Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV SURVEYIN
						Parallaxx Limited PO Box 302473 North Harbour 0751	Telephone: 0800 333 772 Web: www.parallaxx.co.nz Email: info@parallaxx.co.nz		This drawing, the design and concept remain the property of Parallaox limited. Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approval from	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 5 - SHOULDE (ENTERING THE
U	$ \square $							\square	the approving engineer and/or road controlling authority.		

Iane/Shoulder, keeping a es. he working space; Surveyor ele. back of the work vehicle le otherwise static signage legally parked. hours where possible). hours where possible). Inspector or TC or STMS to spotter required DIRECTION AND PROTECTION): backed with beacons on and dertaking the operation. If then select the Advanced ON." If static signs are t TV2 "Pass With Care" for

	DRAWING TITLE:
TING GENERICS	PXJ-9410
DER OR PARKING LANE	SHEET NO:
IE LIVE LANE)	Sheet 5 of 14



OPERATION 6 - LEVEL 1 & LEVEL 2LS ROADS WORKING IN A SHOULDER OR PARKING LANE (ENTERING THE LIVE LANE)

CONDITIONS FOR L2LS ROADS:

- There must be CSD to the work vehicle on Level 2LS roads.
- Special RCA approval can be obtained to use Level 1 static signage on Level 2LS roads if CSD is not achievable.

CONDITIONS FOR L1 ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space: Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required

VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):


• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. If there is CSD to the work vehicle then select the Advanced Warning sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

EXTRA SAFETY DEVICES:

• A 10m taper must be installed, with a longitudinal safety zone as per distance layout table attached, the work vehicle MUST be included in the working space and a 1m lateral safety zone maintained around the working space, cones to delineate the length of the working space. Apply all other notes above.

1)								
	Rev	Denciption	άý	Child	Date	DRAWING ORIGINATOR:	ORIGINAL SCALE		PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G.	D.L.	22/05/20			Antonette Galang (Level 2/3 NP, #129806, 10/01/2022)		
						PARALI A 🗙 👘	M T C	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		L1/L2LS SURVEYING
	\square						N.I.S	This drawing, the design and concept remain the property of	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 6 - SHOULDER
	\vdash			-	<u> </u>	Parallaxx Limited Telephone: 0800 333 772	11	Parallaxx Limited. Unauthorised reproduction of any part of this document is		I OF ERWITCH OF CHOOLDER
						PO Box 302473 Web: www.parallaxx.co.nz		prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at		CENTERING THE LIV
J						North Harbour 0751 Email: info@parallaxx.co.nz		the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		

DRAWING TITLE: PXJ-9410 NG GENERICS R OR PARKING LANE SHEET NO: Sheet 6 of LIVE LANE) 14



OPERATION 7 - LR/LV, & LOW VOLUME ROADS WORKING WHERE THERE IS NO EDGE LINE OR INFERRED EDGE LINE TRIPOD STRADDLING THE KERB & CHANNEL OVERTAKING VEHICLES NOT CROSSING CENTRELINE OR ENTERING THE FLUSH MEDIAN (NOT ENTERING THE LIVELANE)

CONDITIONS FOR LV ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).


PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required

VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. If there is CSD to the work vehicle then select the Advanced Warning sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

	RIGINAL IN COLOUR												
Rev	Deveciption	ம் பங	Date	DRAWING ORIGINATOR:	J	ORIGINAL SCALE:		PREPARED FOR CLENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:	DRAWING TITL	E:		
1	INITIAL DRAWING	A.G. D.L.	22/05/20		AX	мтс	Antonette Galang (Level 2/3 NP, #129806, 10/01/2022) Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV SURVEYING GENERICS	P	XJ-9	9410)
				Parallaxx Limited PO Box 302473	Telephone: 0800 333 772 Web: www.parallaxx.co.nz	N.I.S	This drawing, the design and concept remain the property of Parallaox limited. Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 7 - NO EDGE LINE OR INFERRED EDGE LINE (NOT ENTERING THE LIVE LANE)	sheet no: Sheet	7	of	14
Ľ				North Harbour 0751	Email: info@parallaxx.co.nz		the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.				<u>′</u>		



OPERATION 8 - LEVEL 1 AND LEVEL 2LS ROADS WORKING WHERE THERE IS NO EDGE LINE OR INFERRED EDGE LINE TRIPOD STRADDLING THE KERB & CHANNEL **OVERTAKING VEHICLES NOT CROSSING CENTRELINE** OR ENTERING THE FLUSH MEDIAN (NOT ENTERING THE LIVELANE)

CONDITIONS FOR L2LS ROADS:

- There must be CSD to the work vehicle on level 2LS roads.
- Special RCA approval can be obtained to use Level 1 static signage on Level 21s roads if CSD is not achievable.

CONDITIONS FOR L1 ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD TO Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required.

VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. if there is CSD to the work vehicle then select the Advanced Warning Sign TV3 "ROAD INSPECTION." if static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

EXTRA SAFETY DEVICES:

• a 10m taper must be installed, with a longitudinal safety zone as per distance layout table attached, the work vehicle MUST be included in the working space and a 1m lateral safety zone maintained around the working space, cones to delineate the length of the working space. Apply all other notes above.

- 1	_									
	Rev	Description	ΰŷ	Chika	f Date	DRAWING ORIGINATOR:	ORIGINAL SCALE	DRAWN & CHECKED BY:	PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G.	D.L.	22/05/		11	Antonette Galang (Level 2/3 NP, #129806, 10/01/2022)		I 4 / DIS SUBVEVIN
			Γ			I PARALI A 🗙 👘	MITC	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		L1/L2LS SURVEYIN
							N.I.S	This drawing, the design and concept remain the property of Parallaxx limited	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 8 - NO EDGE LINE
						Parallaxx Limited Telephone: 0800 333 772		Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at		(NOT ENTERING THE
l				\square		PO Box 302473 Web: www.parallaxx.co.nz North Harbour 0751 Email: info@parallaxx.co.nz		the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		(NOT ENTERING THE
· · ·			_	_	-					

DRAWING TITLE-


SHEET NO:

PXJ-9410

Sheet 8 of

ING GENERICS OR INFERRED EDGE LINE HE LIVE LANE)

ustry_tmd.dwg 0:1-94:0



OPERATION 9 - LR/LV AND LOW VOLUME ROADS WORKING WHERE THERE IS NO EDGE LINE OR INFERRED EDGE LINE **TRIPOD STRADDLING THE KERB & CHANNEL OVERTAKING VEHICLES NOT CROSSING CENTRELINE** OR ENTERING THE FLUSH MEDIAN (ENTERING THE LIVE LANE)

CONDITIONS FOR LV ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD to Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).


PERSONNEL REQUIRED:

• Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required

VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):

• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. if there is CSD to the work vehicle then select the Advanced Warning Sign TV3 "ROAD INSPECTION." If static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

C	DRIGINAL IN COLOUR		_								
Re	Description	the Child	Date	DRAWING ORIGINATOR:)	ORIGINAL SCALE:	DRAWN & CHECKED BY:	PREPARED FOR CLENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:	DRAWING TITLE	
1	INITIAL DRAWING	A.G. D.L.	22/05/20		AX	NTC	Antonette Galang (Level 2/3 NP, #129806, 10/01/2022) Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV SURVEYING GENERICS	PXJ-9410	ſ
				Parallaxx Limited PO Box 302473 North Harbour 0751	Telephone: 0800 333 772 Web: www.parallaxx.co.nz Email: info@parallaxx.co.nz	N.I.3	This drawing, the design and concept remain the property of Parallaxa Limited. Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approval from the approving enimeer and/or road controlling authority.	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 9 - NO EDGE LINE OR INFERRED EDGE LINE (ENTERING THE LIVE LANE)	sheet ND Sheet 9 of	14



OPERATION 10 - LEVEL 1 & LEVEL 2LS WORKING WHERE THERE IS NO EDGE LINE OR INFERRED EDGE LINE **TRIPOD STRADDLING THE KERB & CHANNEL OVERTAKING VEHICLES NOT CROSSING CENTRELINE** OR ENTERING THE FLUSH MEDIAN (ENTERING THE LIVE LANE)

CONDITIONS FOR L2LS ROADS:

- There must be CSD to the work vehicle on level 2LS roads.
- Special RCA approval can be obtained to use Level 1 static signage on Level 21s roads if CSD is not achievable.

CONDITIONS FOR L1 ROADS:

- Surveyor can access the Parking lane/Shoulder, keeping a 1m lateral safety zone at all times.
- Work vehicle is not included in the working space; Surveyor must work in front of work vehicle.
- Signage may be attached to the back of the work vehicle if CSD TO Work vehicle is available otherwise static signage must be installed while vehicle is legally parked.

TIME RESTRICTIONS:

• No time restrictions (avoid peak hours where possible).

PERSONNEL REQUIRED:

Once briefed by an STMS - TC Inspector or TC or STMS can carry out this operation - no spotter required.

VEHICLE (ADVANCED WARNING OR DIRECTION AND PROTECTION):


• Vehicle must always be legally parked with beacons on and a vehicle mounted sign while undertaking the operation. if there is CSD to the work vehicle then select the Advanced Warning Sign TV3 "ROAD INSPECTION." if static signs are being installed, then please select TV2 "Pass With Care" for the back of the work vehicles.

EXTRA SAFETY DEVICES:

• a 10m taper must be installed, with a longitudinal safety zone as per distance layout table attached, the work vehicle MUST be included in the working space and a 1m lateral safety zone maintained around the working space, cones to delineate the length of the working space. Apply all other notes above.

_	_										
A	*	Description	άŷ.	Child	Da	•	DRAWING ORIGINATOR:	ORIGINAL SCALE:	DRAWN & CHECKED BY:	PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G.	D.L.	22/0	5/20			Antonette Galang (Level 2/3 NP, #129806, 10/01/2022)		
							PARALLA 🗶 🛛	NITC	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		L1/L2LS SURVEYII
								N.I.S	This drawing, the design and concept remain the property of Parallaxx Limited.	CONSULTING SURVEYORS NEW ZEALAND	OPERATION 10 - NO EDGE LINE
	+						Parallaxx Limited Telephone: 0800 333 772		Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the		
	+						PO Box 302473 Web: www.parallaxx.co.nz North Harbour 0751 Email: info@parallaxx.co.nz		associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		(ENTERING THE L
	_		_			_		-			<u></u>

DRAWING TITLE-PXJ-9410 YING GENERICS. NE OR INFERRED EDGE LINE SHEET NO: Sheet 10 of LIVE LANE)



LOW VOLUME & LEVEL 1 TWO-WAY TWO-LANE ROAD (J2.16a) SHORT NO EXIT ROAD


TG2 signs required on main road.

worksite where there is less than working space to the end of the

EYING	GENERICS
ROAD	(J2.16a)
D—LANE	ROAD

P	YJ-9	9410	
SHEET NO:			
Sheet	11	of	14

DRAWING TITLE-




for the surveying industry_tmd.dwg copttm ı px1-9410

14

P	YJ-9	9410
SHEET NO:		
Sheet	12	of

DRAWING TITLE:



LR/LV, LOW VOLUME, LEVEL 1, & LEVEL 2 ROADS FOOTPATH DIVERTED ONTO BERM BEHIND WORKING SPACE (F2.1A)

<u>NOTES:</u>


- Minimum pedestrian footpath widths: *Residential/Rural/Suburban Centre - 1.2m *CBD - 2m
- 2. Where the length of the temporary footpaths exceeds 20m, these widths may have to be increased so footpath users do not have to wait to pass.
- 3. Temporary footpath surfaces must be suitable for footpath users.
- 4. Use safety fence to enclose the working space, or at attended worksites, cones connected with cone bars can be used to enclose the working space but only for a short period of time. NOTE: Cone bars are not recommended where heavy equipment (e.g. a digger) is being used. A safety fence is preferred in these cases.
- 5. This TMD must be used in conjunction with appropriate TTM for any work carried out on the shoulder or in the live lane.

l	OR	RIGINAL IN COLOUR		-							
1	Rev	Description	Ъў.	Child	Date	DRAWING ORIGINATOR:		ORIGINAL SCALE:	DRAWN & CHECKED BY: Antonette Galang (Level 2/3 NP, #129806,	PREPARED FOR CLIENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G.	D.L.	22/05/20				10/01/2022)		
						DADAH	$\land \mathbf{W}$	NTC	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV/L1/L2 SU
							~ ~	N.I.5	This drawing, the design and concept remain the property of Parallaxx Limited.	CONSULTING SURVEYORS NEW ZEALAND	FCOTPATH CIVERTED
						Parallaxx Limited	Telephone: 0800 333 772		Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the		
						PO Box 302473 North Harbour 0751	Web: www.parallaxx.co.nz Email: info@parallaxx.co.nz		associated Traffic Management Plan) must be utilised only at the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		BEHIND WOR
G								-	the approving engineer analysi road controlling dationity.	۱ <u>ــــــــــــــــــــــــــــــــــــ</u>	

widths: Centre - 1.2m Dorary footpaths hay have to be do not have to wait must be suitable for the working space, or connected with cone the working space of time. ommended where er) is being used. A hese cases. onjunction with carried out on the

RVEYING GENERICS ONTO EERM (F2.1A) RKING SPACE

F	vXJ-8	9410	1
SHEET NO:			
Sheet	13	OÍ	14



LR/LV, LOW VOLUME, LEVEL 1, & LEVEL 2 ROADS FOOTPATH DIVERTED ONTO BERM BETWEEN WORKING SPACE AND CARRAIGEWAY (F2.2a)

NOTES:

- Minimum pedestrian footpath widths: *Residential/Rural/Suburban Centre - 1.2m *CBD - 2m
- 2. Where the length of the temporary footpaths exceeds 20m, these widths may have to be increased so footpath users do not have to wait to pass.
- 3. Temporary footpath surfaces must be suitable for footpath users.
- 4. Use safety fence to enclose the working space, or at attended worksites, cones connected with cone bars can be used to enclose the working space but only for a short period of time. NOTE: Cone bars are not recommended where heavy equipment (e.g. a digger) is being used. A safety fence is preferred in these cases.
- Use barrier or safety fence to delineate the traffic side of the footpath, or at attended worksites cones connected with cone bars can be used to delineate the traffic side of the footpath for a short period of time (not for use on state highways)
- 6. There must be a lateral safety zone between the traffic side of the footpath and the live lane: *0.5m for barrier
- *1m for safety fence or cone bars
 7. This TMD must be used in conjunction with appropriate TTM for any work carried out on the shoulder or in the live lane.

ľ	OF										
6	Rev	Denciption	άŷ	Child	Date	DRAWING ORIGINATOR:		ORIGINAL SCALE:		PREPARED FOR CLENT / CONTRACTOR / PROJECT / CONTRACT:	DRAWING TITLE:
	1	INITIAL DRAWING	A.G	D.L.	22/05/20				Antonette Galang (Level 2/3 NP, #129806, 10/01/2022)		
						I DARAL I	AX	MIC	Diana Lising (Level 2/3 NP, #110586, 20/08/2022)		LR/LV/L1/L2 SURV
								N.I.S	This drawing, the design and concept remain the property of Parallaxx Limited.	CONSULTING SURVEYORS NEW ZEALAND	FOOTPATH CIVERTED (
						Parallaxx Limited PO Box 302473	Telephone: 0800 333 772 Web: www.parallaxx.co.nz		Unauthorised reproduction of any part of this document is prohibited. This Traffic Management Drawing (with the associated Traffic Management Plan) must be utilised only at		BETWEEN WORKING SPA
l						North Harbour 0751	Email: info@parallaxx.co.nz		the location(s) it is associated and not without approval from the approving engineer and/or road controlling authority.		

RVEYING GENERICS ONTO EERM (F2.2A) PACE & CARRIAGEWAY

Р	XJ-8	9410	
sheet no: Sheet	14	0ť	14

DRAWING TITLE:

-		s for generic TMPs and On-Site Re															
This form, or a similar company record, must be completed prior to set up of a worksite where a generic TMP is used. Location details																	
Location	n details						T										
Road name(s)	Location	n #1	House														
	Location	n #2	<u> </u>				number/RP(s) House						Suburb				
	Location							umber/RP(s)									
Generic TMP reference no.			тм										Note: The checking process must include all the TMDs to be used				
Person i	in charge	of the TTM						T									
TCi - P																	
		Name	Name				NZTA ID Number			xpiry d	ate	Signature				Briefing completed	
Site L	landovar	to															
Site Handover t another TCi - P							NZTA ID Number			xpiry d	ate	Signature			Briefing received		
		Time handover briefing comple	Time handover briefing completed														
Are the	Are the following catered for in the generic TMP?					Location #1	L			Locat	ation #2			Location #3			
Catego	ry	Points to consider	Y	Ν		Comment/	Mitigation		Y	N	Con	nment/Mitigation	Y	Ν	Co	mment/Mitigation	
RCA notifica		Has the RCA been notified?															
Road le	evel	Is this at the correct road level?															
Shape		Intersections, Hills, Horizontal Curves, Enough advance warning															
		Can you park/place equipment as per the TMD?															
Directic protect	on and	Enough road width for road user?i.e. minimum lane width is 2.75madequate sight distance on both sides															
Plant ar equipm	ient	Will your plant and equipment fit within the designated working space?															
Person safety		Is there a safe escape route? PPE Worn?															
Layout diagram		Is diagram detailed in the generic TMP fit for purpose and is the															

	operation described in the											
	Proforma?											
RCA notification	Has the RCA been notified?											
Footpath Standards Met?	Footpath blocked?											
Cycle lane	Equipment in the cycle lane?											
standards met?	Car parked in cycle lane?											
Traffic flows OK?	Operating outside of peak hours											
Adequate property access?	Driveway blocked?											
Time assess												
Site Supervi												
Additional C												
Personnel B	Name:				Signature:				Date/Time:			